

WS610a

AT ref: 007B

issued by

M. Vernon

Ref	Street	Species	Requirement Note	Priority	Requirement	option	TPO	reasons
09BA	CHIMSWELL WAY	Quercus robur	Crown lift to 2.5m above ground level over drive and mown grass.	12 months	Crown Lifting/Raising		192(1993) A1	maintain reasonable clearance below crown
09BB	CHIMSWELL WAY	Acer campestre, Crataegus monogyna, Fraxinus excelsior, Prunus sp., Quercus robur	Crown lift to 4m over drive, 2.5m over footpath & mown grass.	12 months	Crown Lifting/Raising		192(1993) A1	maintain reasonable clearance below crown
09BL	ATTERTON ROAD	Fraxinus excelsior		12 months	Crown Lifting/Raising	To 2.5m	192(1993) A2	maintain reasonable clearance below crown
09BL	ATTERTON ROAD	Fraxinus excelsior		12 months	Climbing Plant: Sever - 1 Tree		192(1993) A2	exempt
09BL	Gainsborough Road	Fraxinus excelsior		12 months	Climbing Plant: Sever		192(1993) A2	exempt
09BL	Gainsborough Road	Fraxinus excelsior		12 months	Crown Lifting/Raising	To 2.5m	192(1993) A2	maintain reasonable clearance below crown
08FQ	PARK ROAD	Crataegus monogyna, Fraxinus excelsior	Crown lift to 2.5m above ground level over the mown grass area to the east.	12 months	Crown Lifting/Raising		192(1993) A2	maintain reasonable clearance below crown
08FQ	PARK ROAD	Crataegus monogyna, Fraxinus excelsior	Crown lift to 2.5m above ground level over the mown grass area to the east.	12 months	Crown Lifting/Raising		192(1993) A2	maintain reasonable clearance below crown

08A3	CHIMSWELL WAY	Acer campestre, Corylus colurna, Crataegus monogyna, Prunus sp., Ulmus glabra	Coppice wind blown blackthorn next to dog waste bin to west of 23 Henderson Close. Fell dead ash and elm within the group. Crown lift to 2.5m above ground level over short grasses areas either side of the group. Prune to clear streetlight A1236 by 1m.	12 months	SE Day Works - Per Hour		192(1993) A3	maintain reasonable clearance below crown and from structures. Dead & windblow exempt
08FR	ATTERTON ROAD	Salix alba	Pollard to previous points, retaining some smaller branches as sap risers.	12 months	SE Pollard: Frequent		192(1993) G1	reduce risk of failure
08FS	ATTERTON ROAD	Fraxinus excelsior	reduce by up to 6m to create pollard points <200mm diameter	3 months	SE Crown Reduction & Reshaping - 1 Tree		192(1993) G1	reduce risk of failure
08FS	ATTERTON ROAD	Fraxinus excelsior		12 months	Climbing Plant: Sever - 1 Tree		192(1993) G1	exempt
08FS	ATTERTON ROAD	Fraxinus excelsior		3 months	Crown Lifting/Raising - 1 Tree	To 2.5m	192(1993) G1	maintain reasonable clearance below crown

08FU	ATTERTON ROAD	Fraxinus excelsior		12 months	Crown Lifting/Raising - 1 Tree	To 2.5m	192(1993) G1	maintain reasonable clearance below crown
08FW	ATTERTON ROAD	Fraxinus excelsior		12 months	Climbing Plant: Sever - 1 Tree		192(1993) G1	exempt
08FW	ATTERTON ROAD	Fraxinus excelsior	Reduce in height by 2m. Reduce lowest lateral on southern aspect by 2m.	12 months	SE Crown Reduction & Reshaping - 1 Tree		192(1993) G1	reduce risk of failure
08FX	ATTERTON ROAD	Fraxinus excelsior		12 months	Climbing Plant: Sever - 1 Tree		192(1993) G1	exempt
08FX	ATTERTON ROAD	Fraxinus excelsior	Reduce in height by approximately 2-2.5m.	12 months	SE Crown Reduction & Reshaping - 1 Tree		192(1993) G1	reduce risk of failure
08FY	ATTERTON ROAD	Fraxinus excelsior	Crown reduce shortening branches by approximately 2m.	12 months	SE Crown Reduction & Reshaping - 1 Tree		192(1993) G1	reduce risk of failure
08G1	ATTERTON ROAD	Fraxinus excelsior	Crown lift to 5m above ground level over the road.	12 months	Crown Lifting/Raising - 1 Tree	To 2.5m	192(1993) G2	maintain reasonable clearance below crown
08G2	ATTERTON ROAD	Fraxinus excelsior	Shorten to 1m stub & leave with fracture cut the declining limb over the car park	12 months	SE Day Works - Per Hour		192(1993) G2	reduce risk of failure
08G4	ATTERTON ROAD	Acer campestre, Crataegus monogyna, Fraxinus excelsior	crown lift to 2.5m above ground level over mown grass areas and car park.	12 months	Crown Lifting/Raising		192(1993) G2	maintain reasonable clearance below crown

08G6	HENDERSON CLOSE	Fraxinus excelsior		12 months	Crown Lifting/Raising - 1 Tree	To 2.5m	192(1993) G3	maintain reasonable clearance below crown
08G6	HENDERSON CLOSE	Fraxinus excelsior		12 months	Climbing Plant: Sever - 1 Tree		192(1993) G3	exempt
08GE	HENDERSON CLOSE	Acer campestre,Crataegus monogyna,Fraxinus excelsior,Prunus sp.,Lireodendron tulipifera,Ulmus glabra	Crown lift to 2.5m over mown areas.	12 months	Crown Lifting/Raising		192(1993) G3	maintain reasonable clearance below crown
08SC	HENDERSON CLOSE	Quercus robur	Crown lift to 2.5m over mown areas.	12 months	Crown Lifting/Raising - 1 Tree		192(1993) G3	maintain reasonable clearance below crown
0911	HENDERSON CLOSE	Quercus robur	Crown lift to 2.5m over mown area.	12 months	Crown Lifting/Raising		192(1993) G3	maintain reasonable clearance below crown
08GJ	HENDERSON CLOSE	Fraxinus excelsior		12 months	Crown Lifting/Raising - 1 Tree	To 2.5m	192(1993) G4	maintain reasonable clearance below crown
08GK	HENDERSON CLOSE	Fraxinus excelsior		12 months	Crown Lifting/Raising - 1 Tree	To 2.5m	192(1993) G4	maintain reasonable clearance below crown
08GM	HENDERSON CLOSE	Acer campestre,Crataegus monogyna,Fraxinus excelsior,Prunus sp.,Ulmus glabra	Streetlight A124	12 months	Clear Street Furniture	By 1m	192(1993) G4	maintain clearance from structures

08GM	HENDERSON CLOSE	Acer campestre,Crataegus monogyna,Fraxinus excelsior,Prunus sp.,Ulmus glabra	Crown lift to 2.5m above ground level over footpaths and mown areas.	12 months	Crown Lifting/Raising	To 2m	192(1993) G4	maintain reasonable clearance below crown
------	--------------------	--	---	-----------	--------------------------	-------	-----------------	---