

NOTES

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEERS, ARCHITECTS AND SPECIALISTS DRAWINGS AND THE SPECIFICATION.
2. **DO NOT SCALE** FROM THIS DRAWING MANUALLY OR ELECTRONICALLY. WRITTEN PERMISSION MUST BE OBTAINED FROM MLM PRIOR TO SCALING ELECTRONICALLY OR USING THIS ELECTRONIC FILE.

CONSTRUCTION (DESIGN AND MANAGEMENT) REGULATIONS 2007 DESIGNERS HAZARD INFORMATION FOR CONSTRUCTION

1. IF YOU DO NOT FULLY UNDERSTAND THE RISKS INVOLVED DURING THE CONSTRUCTION OF THE ITEMS INDICATED ON THIS DRAWING ASK YOUR MANAGER, HEALTH & SAFETY ADVISOR OR A MEMBER OF THE DESIGN TEAM BEFORE PROCEEDING.

THE ABOVE NOTES REFER SPECIFICALLY TO THE INFORMATION SHOWN ON THIS DRAWING. REFER TO THE HEALTH AND SAFETY PLAN FOR FURTHER INFORMATION.

Issue	Date	Description	Made	Checked
Drawing Status:				

INFORMATION



Consulting Civil, Structural & Building Services Engineers
 190 Eureka Park, Upper Pemberton, Ashford TN25 4AZ
 Tel: 01233 610530 Fax: 01233 618299
 Website: www.mlm.uk.com


Client
 Cambridge * Chelmsford * Ipswich * London * Norwich

NORTH WEST HAVERHILL LANDOWNERS CONSORTIUM


Project
NORTH WEST HAVERHILL URBAN EXTENSION

Drawing Title
PRELIMINARY LEVELS SHEET 2 of 2

Drawn/Design	CHK	Checked	JEB	Approved	...	Date
1:1250 @ A1						17.09.10
1:2500 @ A3						
Drawing No.						612263/C/002
Rev						



NOTE: ALL LEVELS AND FINISHED FLOOR LEVELS ARE PRELIMINARY BASED ON THE TOPOGRAPHICAL SURVEY LEVELS PLUS AN AVERAGE FILL OF 0.345m. ALL LEVELS ARE TO BE CONFIRMED AT DETAILED DESIGN STAGE.



CUT AND FILL NOTES	ITEM	VOLUME OF CUT (m3)
	ADAPTABLE SURFACE WATER	16,891
	ADAPTABLE FOUL WATER	12,429
	TANKS AND PONDS ETC.	9,469
	RETENTION WALLS	17,732
	FOUNDATIONS	12,792
	ON SITE ROADS	39,859
	ON SITE HARDSTANDINGS	20,617
	RELIEF ROAD	12,479
TOTAL CUT		134,795
TOTAL SITE AREA = 39.0977ha = 390,977m2		
THEREFORE:		
134,795 / 390.977 = 0.345M (DEPTH OF FILL REQUIRED)		
NOTE: THE ABOVE VALUES ARE APPROXIMATE ONLY AND ARE TO BE CONFIRMED AT DETAILED DESIGN STAGE		