THIS DRAWING IS TO BE READ IN CONJUNCTION WITH SEPERATE GROUP / SITE SPECIFIC CONSTRUCTION NOTES AND MATERIALS SPECIFICATION.



LEGEND

- EASEMENT
- EXISTING TREES/HEDGES
  With Root Protection Area
  To be Retained
- PROPOSED TREES
  Select/Standard/Heavy Standard
  See Schedule
- PROPOSED TREES
  Conifers
  See Schedule
- ORNAMENTAL HEDGE
  See Schedule
  TOTAL LENGTH: 1574m
- NATIVE HEDGE
  See Schedule
  TOTAL LENGTH: 2370m
- PROPOSED PLANTING
  Shrubs/Herbaceous/Grasses
  See Schedule
- TURF
  TOTAL AREA: 7600m²
- AMENITY GRASS AREAS
  Emorsgate EG22 sown at 25g/m²
  Kept mown short to 40mm
  TOTAL AREA: 1200m²
- WILDFLOWER MEADOW
  Emorsgate EM3 sown at 4 g/m²
  TOTAL AREA: 24,700m²
  (Existing grassland to be retained and managed. Where remediation is required sow as above)
- WILDFLOWER MEADOW MOWN PATH
- SEASONAL WETLANDS
  Emorsgate EM8 sown at 4 g/m²
  TOTAL AREA: 8050m²
- WOODLAND MIX
  See Schedule
- SENSORY MIX
  See Schedule
- POND EDGE MIX
  See Schedule
- MARGINAL MIX
  See Schedule
- AMENITY MIX
  See Schedule
- GRAVEL
  40mm of Stone over Membrane
- ROOT BARRIER - 600mm Depth
  Can be a depth of 300mm, if services are more than 900mm away from the back edge of footpath (tree side)

GREAT WILSEY PARK

Job. Great Wilsey Park, Haverhill Parcels A9, A14, A15, B2, E2

Title. SITE OVERVIEW

Scale. 1:500 @ A0	Drawn. EP
Date. Jan 2025	Checked. PmJ

THIS DRAWING AND THE BUILDING WORKS DEPICTED ARE THE COPYRIGHT OF J.S.BLOOR (SERVICES) LIMITED AND MAY NOT BE REPRODUCED OR AMENDED EXCEPT BY WRITTEN PERMISSION. NO LIABILITY WILL BE ACCEPTED FOR AMENDMENTS MADE BY OTHER PERSONS

BLOOR HOMES
J S BLOOR (SERVICES) LIMITED
ASHBY ROAD, MEASHAM, SWADLINCOTE, DERBYSHIRE DE12 7JP
TELEPHONE 01530 270100 FACSIMILE 01530 272006

Drawing No. EA232-LS-016